

# **Smart Grid Interconnections, Communications and Implementation**

New Energy Forum (NEF)  
2013

# New Energy Forum



1. Solar Energy
2. Wind Energy
3. **Energy Storage and Smart Grid Technologies**
  1. Energy Storage Market and Technologies
  2. Smart Grid Regulation, Policy and Investment
  3. Grid Integration and Energy Storage for Renewable Energies
4. **Smart Grid Interconnections, Communications and Implementation** (8:30 to 8:35)

*September 28, 2013 (Saturday)*

*Chair: Leonhard Korowajczuk- CelPlan International, Inc. , USA*

*Co-Chair: Patrick Avery- G&W Electric Company., USA*

**4.1. Smart Grid Wireless Design Considerations** (8:35 to 9:00)

*Leonhard Korowajczuk- CelPlan International, Inc., USA*

**4.2. Smart City Development in Sino-Singapore Guangzhou Knowledge City** (9:00 to 9:25)

*Nee Pai Chee,- Sino-Singapore Guangzhou Knowledge City, China*

**4.3. Renewable Energy Automation** (9:25 to 9:50)

*Patrick Avery- G&W Electric Co., USA*

**4.4. Smart Grid and Security Analysis in the context of AMI (Advanced Metering Infrastructure)** (9:50 to 10:15)

*Akbar Hussein- Aalborg University, Denmark*

4. Offshore wind energy and marine renewable energy
5. Advances in other New Energy technology
6. Hydrogen Energy
7. Renewable Bio-Energy
8. Nuclear Energy
9. Geothermal Energy

# SMART GRID









- During the last century energy generating plants were interconnected into a GRID
  - Users are energy consumers connected to the GRID
- During this century the increasing power demand will require significant changes to the GRID
  - Users will become power consumers and generators
  - Energy will have to be stored during low demand and used during high demand periods
  - Energy use will have to be more rational and efficient
  - The next-generation power grid has to improve upon the GRID weaknesses, which are:
    - Centralized power generation, with huge losses in transmission lines
    - Lack of coordination between energy production and consumption
    - The GRID has to become a SMART GRID
- This next-generation power network is referred as SMART GRID
- The SMART GRID concept requires an overlaid communications network that:
  - Must be able to reach every point of the interconnected power network
  - Provide wideband communications for real-time usage, performance and automation
  - Provide adequate reliability and availability
  - Be cost effective

# Presenter



- **Leonhard Korowajczuk**

- CEO/CTO CelPlan International
- 45 years of experience in the telecom field (R&D, manufacturing and services areas)
- Holds 13 patents
- Published books
  - “Designing cdma2000 Systems”
    - published by Wiley in 2006- 963 pages, available in hard cover, e-book and Kindle
  - “LTE , WiMAX and WLAN Network Design, Optimization and Performance Analysis ”
    - published by Wiley in June 2011- 750 pages, available in hard cover, e-book and Kindle
- Books in Preparation:
  - LTE , WiMAX and WLAN Network Design, Optimization and Performance Analysis
    - second edition (2012) LTE-A and WiMAX 2.2
  - Network Video: Private and Public Safety Applications (2013)
  - Backhaul Network Design (2014)
  - Multi-Technology Networks: from GSM to LTE (2014)
  - Smart Grid Network Design (2014)





# CelPlan International



- *CelPlan has rapidly established itself as an innovative leader in providing the most advanced engineering solutions for the wireless industry.*
- *CelPlan brings a powerful and sophisticated portfolio of software and engineering capabilities to bear on the design and development of next generation wireless*

- **Smart Grid require Wireless Network Planning Solutions and Engineering Services for**
  - Advanced Metering Infrastructure (AMI)
  - Advanced Distribution Automation (ADA)
  - M2M Communications
  - Smart Grid
  - Intelligent Grids
- **Wireless Network Design for Critical Infrastructure**
  - Designs should be done for wireless networks with specific latency and reliability goals to enable the deployment of power grid automation and other sensitive operations in Critical Infrastructure environments
  - Typical network specifications used during the design & planning exercises are:
    - Reliability: > 99.99%
    - Availability: > 99.999%
    - Latency: < 20 ms



# Smart Grid Wireless Design Considerations

Designing for  
Reliability - Availability - Latency


New Energy Forum  
(NEF)  
2013

Leonhard Korowajczuk  
CEO/CTO  
CelPlan International, Inc.  
[www.celplan.com](http://www.celplan.com)  
[leonhard@celplan.com](mailto:leonhard@celplan.com)  
Skype: leonhard.k  
1-703-259-4022

# Smart Grid Wireless Architecture



# Smart Grid Wireless Architecture



# Smart Grid Architecture



- Remote Units
- Interconnection Network
  - Communications Network
  - Communication Network Technology

# Architecture- Remote Units

- Remote Terminal Unit (RTU)
  - Distribution Automation (DA): up to 10,000 RTU
    - Polling and autonomous messaging (RTU: 1kbps)
    - Mission Critical (Latency: < 20 ms, Availability: 99.999%)
    - DH (Design Hour) total traffic: 10 Mbit/s
  - Advanced Metering Infrastructure (AMI)- up to 10,000,000 RTU
    - Polling (RTU: 10 bps)
    - Non mission critical (Latency: non critical, Availability: 99.0%)
    - DH total traffic: 100 Mbit/s
  - Mobile Force (MF): 5,000 RTU
    - Low throughput conversational and text (RTU: 1 kbps)
    - Non mission critical (Latency: conversational , Availability: 99.9%)
    - DH total traffic: 5 Mbit/s
  - Video Network (VN): 1,000 RTU
    - High throughput uplink (2 Mpixel, 1 fps, H.264 ): (RTU: 1 Mbps)
    - Non mission critical (Latency: video, Availability: 99.9%)
    - DH total traffic: 1 Gbit/s

# Architecture- Interconnection Network

- Last Mile (LM) Concentration Points (CP)
  - Point to Multipoint (PtM) non LOS (non Line of Sight)
  - Latency: non critical (100 ms)
  - Availability: 99.99%
- Middle Mile (MM) Concentration Points (CP)
  - Point to multipoint mainly LOS (Line of Sight)
  - Latency: 20 ms
  - Availability: 99.9999%
- High capacity Backhaul
  - Point to Point (PtP) LOS
  - Latency: 10 ms
  - Availability: 99.99999%

# Communications Network



- Commercial
  - Not recommended for last mile (LM) or middle mile (ML)
  - Throughput can not be guaranteed
  - May be considered as a temporary solution
- Proprietary
  - Requires spectrum availability
  - May be expensive
  - Full control
- Shared
  - Provisioned by third party
  - Some implementations allow for bandwidth segregation
  - Growth and expansion may be tricky

- Cable / ADSL
- All-Dielectric Self Supporting (ADSS) fiber
- Optical Ground Wire (OPGW)
  - Fiber to the Home (FTTH)
  - Fiber to the Node (FTTN)
- Wireless over Power Line
- Licensed Point to Multipoint Wireless / Point to Point Wireless
  - Cellular
  - Satellite
  - WiMAX/LTE
  - Proprietary

## Alternatives

- VHF and UHF Narrow Band (SCADA)
  - 12.5 to 50 kHz bandwidth
  - 100 kbps marketing throughput
- Commercial Cellular
  - Cdma2000, EVDO
  - GSM, EDGE, HSPA
  - Wi-Fi
    - Contention based protocol
    - Throughput drops exponentially with number of users, mainly in mesh configurations
- Satellite
  - Limited throughput
  - Emergency situations
- OFDM Based (4G)
  - WiMAX
    - 200 kHz to 20 MHz
    - Up to 8 MBps (10 MHz TDD)
    - Based on commercial IP infrastructure
    - WiGRID specification
  - LTE
    - 200 kHz to 20 MHz
    - Up to 8 MBps (10 + 10 MHz FDD)
    - Based on operator specific infrastructure

# Wireless Communication Technology Alternatives



- The overall solution should be a mix of the listed alternatives
- WiMAX is the most adequate technology
  - Higher spectral efficiency
  - Available for licensed and unlicensed bands
  - TDD oriented
  - Powerful interference avoidance and control
  - Possible frequency reuse of 1, through segmentation and zoning
  - Compatible with regular IT infrastructure
  - Best cost to capacity ratio
  - WiGRID specification specially developed for Smart Grids



# Typical System Characteristics



- Reliability
  - Hardware dependable (redundancy)
- Availability
  - Link dependable (redundancy, repetition)
- Latency
  - Delay (confirmation, repetition)

Typical Values							
	Application				Communication		
	AMI	SCADA/MF	DA	Video	LM	MM	Backhaul
Reliability (%)	99.00	99.9	99.999	99.00	99.99	99.999	99.9999
Availability (%)	99.00	99.9	99.999	99.00	99.99	99.999	99.9999
Data Throughput (kbps)	0.01	1	1	1,000	1,000	20,000	100,000
Type	TCP	TCP	TCP	UDP	IP	IP	IP
Latency (ms)	10,000	1,000	25	-	100	20	10
Technology					WiMAX	WiMAX	PM/WiMAX
Band (MHz)					220, 700, 900	2,500, 3,500	6,000, 12,000, 18,000


# Network Design



- A mixed network (Wireline and Wireless) is the best solution
- Broadband Wireless network should be utility owned
  - WiMAX is the best technology
- Robust protocol must be used for Network Automation
- A comprehensive design covering the whole network should be done since the beginning
- A professional design must be done covering all applications

# Network Design

- RF propagation model is used to calculate the average signal level
- M2M traffic is simulated as a load to the technology of choice
- Service area and capacity are determined
- Availability and latency are calculated
- A proper design saves significant amounts (CAPEX and OPEX) along the life of the network



Signal Level (dBm)



Dynamic Traffic Placement Simulation

# Practical Design Examples

Availability Centric Design


Reliability Centric Design

# Availability Centric Design

Design done for an Utility  
Company in Canada  
Focus on Automation


# Wireless Channel

- Data transmission based on IP
- Wireless Channel Signal to Noise Ratio (SNR)
  - LOS (Line of Sight)
  - NLOS (Non Line of Sight)
  - Fading
- Data Protocol Overhead
- Error correction (Forward and Backward)
- Technology Used




# SNR in a Gaussian Channel

- Line of Sight signal is prevalent in this channel



# SNR in a Rayleigh Channel



- No prevalent signal is available, in those none Line of Sight conditions






# Propagation Characterization

- CelSignal test equipment
  - Data collection
  - Moving and static




# Fading distribution

- Typical signal level distribution during measurement at a location




# Data Overhead

- Small packets have a relatively high overhead
- 15 Bytes become 295 Bytes
- Overhead can vary from 3 times to 20 times the data payload



# WiMAX OFDMA data allocation (PUSC)




# Wireless Communications



- Wireless Communications are designed for a certain error rate
- Error correction instances
  - Forward error correction codes (Turbo codes)
  - Backward error correction codes (Check sum)
    - HARQ (Hybrid Automatic Repeat Request)
    - ARQ (Automatic Repeat request)
  - Message repetition
    - IP- Internet Protocol (no error correction)
    - TCP- Transmission Control Protocol (error correction)
    - UDP- User Datagram Protocol (no error correction)


# Availability Margins

- Wireless Signal Availability



# Availability

- Signal Level Thresholds
  - Noise Floor
  - Noise Rise (due to interference)
  - SNR Margin required by modulation scheme for environment type
  - Average received Signal Level and its statistical distribution
- Margin for availability
  - Defines number of 9s



# Signal Level x Availability



- Signal Level Thresholds for 3, 4 and 5 nines availability, considering 1 HARQ cycle

				1 HARQ cycle			
Availability (%)	Error Rate	SNR for QPSK1/2 rep 2 (dB)	Fading std (dB)	number of std	Margin (dB)	Noise Floor +Noise Rise (dBm)	Average Signal Threshold (dBm)
99	$10^{-2}$	5	1.44	2.33	8.35	-99	-90.65
99.9	$10^{-3}$	12	1.44	3.09	16.45	-99	-82.55
99.999	$10^{-5}$	25	1.44	4.27	31.14	-99	-67.86



# Signal Level x Availability x Latency




- Signal Level Thresholds for 3, 4 and 5 nines availability, considering 2 HARQ cycle

				2 HARQ cycle			
Availability (%)	Error Rate	SNR for QPSK1/2 rep 2 (dB)	Fading std (dB)	number of std	Margin	Noise Floor +Noise Rise (dBm)	Average Signal Threshold (dBm)
99	$10^{-2}$	5	1.44	1.28	6.85	-99	-92.15
99.9	$10^{-3}$	12	1.44	1.86	14.67	-99	-84.33
99.999	$10^{-5}$	25	1.44	2.73	28.93	-99	-70.07

# Latency x HARQ

- Latency for WiMAX TDD

- Function of frame size



# Latency

- Requirement: 30 ms
- One HARQ cycle: 15 ms
- Two HARQ cycles: 25 ms
- One ARQ cycle: 50 ms

	Earliest (frames)	Latest (frames)
First HARQ cycle	2	3
Extra HARQ cycle	1	2
ARQ cycle	4	6

# Reliability Centric Design

Design done for a Mineral Extraction  
Company in Brazil  
Focus on Reliability


# Reliability



- Ore extraction project in North East of Brazil required a reliable high throughput communication system
- WiMAX technology was chosen due to its features, like TDD, fading resilience, flexible data size, segmentation and non proprietary fully IP based infrastructure.
- CelPlan did the design and frequency plan complying with all network requirements
  - Network continues to operate even with two simultaneous failures

# Iron Ore Extraction

- Ore is extracted, loaded on trains and transported to the port area



# Iron Ore Storage

- Ore is stored until ships are available for transportation



# Iron Ore Loading

- Ore is loaded on conveyor belts and transported to ships





# Iron Ore Loading

- Monstrous machines on rails process and load the ore
- Operator has limited vision inside the machine and relies on several high definition video cameras to operate
- Environment inside the machines is noisy, vibrating and highly susceptible to equipment damage



# Remote Machine Command



- The command of each machine was transferred to an operation Center
- The cost of a non operational machine is very high
- A high Reliability network was required
- Four WiMAX Base Stations were assembled in the periphery of the ore deposit field
- Redundant Video Cameras are able to connect to any of the WiMAX systems
- The system was designed to recover from double failure in each machine and triple failure at the WiMAX nodes

# Conclusions

- Smart Grid implementation require a detail characterization of the services to be offered
- The wireless network has to be designed to provide the require QoS (Quality of Service) for each service
- The wireless design will define
  - Technology
  - Site locations
  - Protocol
  - Frequencies, codes and network parameters
- Specialized tools and expertise are required to perform this determinations



CelPlan Technologies  
Leonhard Korowajczuk  
CEO/CTO  
Leonhard @celplan.com  
703-259-4022  
www.celplan.com



Questions?